# MCC Upgrade Projects Since STS-109



DO/J. Cavallaro 3/09/07





- Awareness of changes in MCC configuration changes since STS-109/SM-3B
  - MCC LAN Replacement
  - FCR-1 Build Up
  - Mission Workstation O/S Replacement (MWSOR)
  - Mission Ops Voice Equipment (MOVE)
- Allow team to assess impacts, if any, of those changes





- Converted MCC backbone LAN from fiber, ring architecture to switched ethernet
- Equipment was no longer maintainable
  - Industry switched from fiber to copper
- Requirements were near exceeding capacity
  - Frequent data drops experienced due to network overload
  - Implemented draconian workstation restrictions to ensure data integrity during critical periods
- Increased capacity from 100mbps to 1gbps
  - Still 100mbps to workstations
- MCC flew in final configuration for STS-121 and 115
  - Significant performance increases observed
    - Core switches running < 10% of capacity
    - Previous LAN frequently ran > 27% of capacity, peaking at 45-50%
  - No reported data drops attributable to LAN performance



## **Architecture Comparison**





#### **Proposed LAN Hiearchical Architecture Overview**





- Former FCR-1 converted to Telescience Center in late 90s
  - Following transition to WFCR, facility was under utilized
  - Anticipated growth in ISS science program
- Growth in ISS Flight Control Team size made continued use of the BFCR impossible
  - Several disciplines were sharing consoles
  - Console resources inadequate for Gemini discipline
  - ISS systems growth required additional capability
- Decision made in 2005 to convert TSC back into FCR-1 for ISS FCT





- Needed to provide alternate accommodations for science team
  - 30M/217 selected-had best balance of size and privacy
  - No anticipated use beyond 13A.1, SpaceHab mission
- Table space in 3301 POCC outfitted with workstations to accommodate SpaceHab for 12A.1 and 13A.1
- Space reserved in former BFCR for a potential HST mission, to replace 30M/217





- FCR-1 recommissioned in October 2006
  - Workstations removed from BFCR and installed in FCR-1
- BFCR to be outfitted with new PC based workstations
  - Serve as HST mission support room
  - Support evolving Constellation activities





- MWSOR project initiated based on termination of support by equipment vendors
  - HP sunset on operating system support in June 2007. JSC negotiated a custom support contract that extends until 12/31/2009
  - Workstation hardware is no longer manufactured
- Replacing DEC/Compaq/HP workstation/server hardware with commodity PCs
- DEC based UNIX being replaced with RedHat Enterprise Linux O/S





- Massive software porting effort has been going on since 2005
  - 4 million lines of platform services code
    - PSS provides common MCC functionality
      - Telemetry
      - o **Timing**
      - Command
  - 15 million lines of user code
    - User code provides discipline specific applications
      - Telemetry displays
      - Limit sensing
      - Plotting
- User testing begins in April 2007



**Mission Workstation O/S Replacement** 









- BFCR is being outfitted with new workstations as we speak
  - In addition to serving as an HST mission support facility it be used as a test facility to validate new software
  - MCC will operate in a hybrid configuration for several shuttle flights
  - Rooms may be split DEC/Linux, Disciplines may be split DEC/Linux
  - Each configuration will be tested through user test and simulation before being used in flight
- 3301/POCC also outfitted with Linux workstations for development/test activity
- Installation activity will be spread over the next several years, concluding in late 2008









# **Mission Workstation O/S Replacement**







## **Mission Workstation O/S Replacement**









- Agency wide initiative to replace aging voice equipment with state of the art, commercial off the shelf technology
- Standardize equipment around the agency
- Contract finally awarded, following dispute
- JSC has participated in project reviews, requirements reviews, etc
- User input solicited to ensure system will meet the needs of flight controllers
- JSC will receive a prime and backup system for MCC operations
- Working on transition plan to bridge loops from old to new system during installation phase





						2007			2008				2009			2010	
ID	0	Task Name	Start	Finish	Q3 Q4	Q	1 Q2	2 Q3	Q4	Q1	Q2 0	23 (	Q4	Q1 Q2	2 Q3	Q4	Q1 Q2
362		DVICE/JSC MOVE Project	7/11/06	1/26/11							Ť		-				
363		MOVE Project-Level Activities	7/11/06	3/21/08							3/21						
364	$\checkmark$	Support Re-Evaluation Effort	7/11/06	9/15/06	9/15												
365	$\checkmark$	Vendor Selection	9/22/06	9/22/06	9/22	2											
366	$\checkmark$	Contract Approval / Negotiations	9/25/06	10/6/06	10/6												
367	$\checkmark$	Protest Resolution	10/9/06	1/15/07		L.	/15										
368	$\checkmark$	Re-Negotiations / Team Coordination	1/16/07	2/1/07		ľ	2/1										
369	$\checkmark$	Contract Start-up	2/1/07	2/1/07			2/1										
370	$\checkmark$	Project-Level TIM	2/14/07	2/15/07			2/15										
371		SDR Presentation (Vendor)	3/26/07	3/30/07			3/3	30									
372		CDR Presentation (Vendor)	5/7/07	5/11/07				5/11									
373		First Article Verification (GSFC)	2/4/08	3/21/08		l					3/21						
374		JSC Reviews	6/18/07	6/23/08			6/18	$\sim$			$\sim$	5/23					
375		SFDR	6/18/07	6/18/07				6/1	В								
376		SDDR #1	8/15/07	8/15/07				8	/15								
377		Final Site Survey & TIM with Vendor	9/26/07	10/2/07					10/2	2							
378		Site Architecture Review (SAR) (Vendor)	11/28/07	11/28/07					$\diamond$	11/28							
379		SDDR #2	1/18/08	1/18/08						1/18							
380		SDDR #3	6/23/08	6/23/08			← St	atus [	Date		e	23					
381		Vendor Equipment Deliveries to JSC	9/4/08	4/1/09							9/4		-	4	/1		
382		Delivery 1 On-Dock (2 Switches, 12 LSAs, 230 Keysets)	9/4/08	9/4/08								9 🔾	э/4				
383		Delivery 2 On-Dock (305 Keysets)	12/31/08	12/31/08										12/31			
384		Delivery 3 On-Dock (329 Keysets)	4/1/09	4/1/09										4	/1		
385		JSC Installation Activities	10/10/07	2/16/10				10/10	$\sim$				-	_			2/16
386		Keyset Cabling Cycle	10/10/07	10/13/08				10/10	$\sim$				10	/13			
389		Transition Equipment Cycle	1/24/08	7/11/08					1/24		$\sim$	7/11					
394		MOVE Equipment Cycle	6/12/08	1/19/10		li				6/12	2		-				1/19
395		Facility Mods	6/12/08	8/8/08		ļ				6/12		8/8	8				
398		Delivery 1 Install/Checkout/Operations	9/5/08	3/6/09							9/5	~	-	3/6	i		
403		Delivery 2 Install/Checkout/Operations	1/2/09	10/20/09								1/	/2			10	/20
407		Delivery 3 Install/Checkout/Operations	4/2/09	1/19/10									ľ	4/2			1/19
411		JSC MCC Transition Complete	2/16/10	2/16/10													2/16
412		JSC DVIS Equipment Removal Complete	1/26/11	1/26/11													